

---

# INVITATION FOR BIDS

**September 18, 2008**

**IFB #2009-2266-0911**

City of Newport News  
DEPT OF PURCHASING, OFFICE OF THE PURCHASING DIRECTOR  
2400 Washington Avenue  
Newport News, VA 23607



**Phone: (757) 926-8721/ Fax: (757) 926-8038**

---

## **Bland Boulevard Culvert Replacement**

### **ADDENDUM 1**

**BID DUE: September 23, 2008 at 2:00 P.M.**

Contract Officer:

---

Ayana Fields, Buyer II

Be Advised of the following changes and clarifications to the subject solicitation:

- **Replace Page B-2 with attached page B-2 (Addendum 1)**
- **Replace Page C-3 with attached page C-3 (Addendum 1)**
- **The asphalt thickness shall be 2" SM-9.5A, 6" BM-25.0 and 8" Crushed Stone Base 21B.**
- **The waterline offset of the 16" line is shown on the plans. Waterworks will provide design and detail to the awarded contractor before or at the pre-construction meeting.**
- **Question: Can we close the road at night to work?**  
**Response: No the road in the traffic control plan cannot be closed at any time.**

Company Name: \_\_\_\_\_

Address: \_\_\_\_\_

City/State/Zip: \_\_\_\_\_

Telephone: \_\_\_\_\_ Fax No.: \_\_\_\_\_ E-Mail: \_\_\_\_\_

Fed. Tax ID (or Social Security #): \_\_\_\_\_

Print Name: \_\_\_\_\_ Title: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This form must be signed. All signatures must be original and not photocopies.

**BID**  
**BLAND BOULEVARD CULVERT REPLACEMENT**

<b>ITEM</b>	<b>DESCRIPTION</b>	<b>APPROX. QTY</b>	<b>UNIT</b>	<b>UNIT BID</b>	<b>UNIT TOTAL</b>
1	Mobilization/ Demobilization	1	LS		
2	Construction Stakeout	1	LS		
3	Traffic Control	1	LS		
4	Erosion Control	1	LS		
5	CG-6 Curb and Gutter	200	LF		
6	Removal of Existing (2) -36 inch Metal double pipes and Structures	220	LF		
7	Removal & Replace 15 inch RCP	24	LF		
8	Removal & Replace 18 inch RCP	24	LF		
9	4' x 3' Double Box Culverts	220	LF		
10	VDOT BCD Headwall	2	EA		
11	Waterline Offset	1	EA		
12	Excavation	683	CY		
13	Select Backfill Material	410	CY		
14	VDOT #57 Stone	125	CY		
15	Base Stone Aggregate	94	CY		
16	BM-25.0 Bituminous Base Course	220	SY		
17	SM-9.5 A Bituminous Surface Course	348	SY		
18	Geotextile Fabric	533	SY		
19	Class A1 Riprap	95	CY		
20	Topsoil & Seeding	917	SY		
21	Undercut/Backfill	20	CY		
	<b>TOTAL BID</b>				

**CONTRACT**  
**BLAND BOULEVARD CULVERT REPLACEMENT**

<b>ITEM</b>	<b>DESCRIPTION</b>	<b>APPROX. QTY</b>	<b>UNIT</b>	<b>UNIT BID</b>	<b>UNIT TOTAL</b>
1	Mobilization/ Demobilization	1	LS		
2	Construction Stakeout	1	LS		
3	Traffic Control	1	LS		
4	Erosion Control	1	LS		
5	CG-6 Curb and Gutter	200	LF		
6	Removal of Existing (2) -36 inch Metal double pipes and Structures	220	LF		
7	Removal & Replace 15 inch RCP	24	LF		
8	Removal & Replace 18 inch RCP	24	LF		
9	4' x 3' Double Box Culverts	220	LF		
10	VDOT BCD Headwall	2	EA		
11	Waterline Offset	1	EA		
12	Excavation	683	CY		
13	Select Backfill Material	410	CY		
14	VDOT #57 Stone	125	CY		
15	Base Stone Aggregate	94	CY		
16	BM-25.0 Bituminous Base Course	220	SY		
17	SM-9.5 A Bituminous Surface Course	348	SY		
18	Geotextile Fabric	533	SY		
19	Class A1 Riprap	95	CY		
20	Topsoil & Seeding	917	SY		
21	Undercut/Backfill	20	CY		
	<b>TOTAL BID</b>				