
INVITATION FOR BIDS

June 19, 2009

IFB #2009-6688-0905

City of Newport News
DEPT OF PURCHASING, OFFICE OF THE PURCHASING DIRECTOR
2400 Washington Avenue
Newport News, VA 23607



Phone: (757) 926-8721/ Fax: (757) 926-8038

Canon Boulevard Sewer Trunk Line Improvements Project

ADDENDUM 1

BID DUE: June 30, 2009 at 2:00 P.M.

Contract Officer:

Ayana Fields, Buyer II

Be Advised of the following changes and clarifications to the subject solicitation:

1. The Bid Due Date is hereby changed to June 30, 2009 at 2:00 PM.
- **Manhole "A" on Plan Sheet C1.1 is changed from 48" to 60".**
 - **In the project Technical Specifications, the revision to the Regional Construction Standards adding Type B epoxy coating to the unit price of manholes has been deleted. The current Page TS-1 is deleted and replaced with the attached page TS-1. (Addendum 1)**
 - **Pages B-2, B-3, C-3 and C-4 are deleted and replaced with Pages B-2, B-3, C-3 and C-4 attached. (Addendum 1) Changes have been made to piping and manhole quantity, size, and depth. Also, field applied epoxy Type B coatings have been added as Items 30 and 31.**

Company Name: _____

Address: _____

City/State/Zip: _____

Telephone: _____ Fax No.: _____ E-Mail: _____

Print Name: _____ Title: _____

Signature: _____ Date: _____

This form must be signed. All signatures must be original and not photocopies.

BID

Canon Boulevard Sewer Trunk Line Improvements Project

Item #	Qty	Unit	Description	Unit Price	Total Price
1	310	LF	18" PVC Gravity Sewer Pipe 10-12' Depth, Installed Complete-in-Place		
2	426	LF	18" DIP Gravity Sewer Pipe 10-12' Depth, Installed Complete-in-Place		
3	299	LF	18" DIP Gravity Sewer Pipe 12-14' Depth, Installed Complete-in-Place		
4	375	LF	24" DIP Gravity Sewer Pipe, 12-14' Depth, Installed Complete-in-Place		
5	136	LF	16" DIP Gravity Sewer Pipe 14-16' Depth, Installed Complete-in-Place		
6	372	LF	16" DIP Gravity Sewer Pipe 12-14' Depth, Installed Complete-in-Place		
7	4	EA	48" Dia. Precast Concrete Manhole, 0-6' Deep, Installed Complete-in-Place		
8	19	VF	48" Dia. Precast Concrete Manhole, Additional Depth Over 6', Installed Complete-in-Place		
9	5	EA	60" Dia. Precast Concrete Manhole, 0-6' Deep, Installed Complete-in-Place		
10	4	EA	60" Dia. Precast Concrete Manhole, Straddle-type, 0-6' Deep, Installed Complete-in-Place		
11	65	VF	60" Dia. Precast Concrete Manhole, Additional Depth Over 6', Installed Complete-in-Place		
12	13	EA	Standard Manhole Frame and Cover, Installed Complete-in-Place		
13	1,800	CY	Select Material (CBR 20)		
14	4	EA	Connection to Existing Sanitary Sewer System		
15	1	LS	Dewatering		
16	1	LS	Fire Hydrant Relocation		
17	300	SF	Pavement Demolition & Replacement Canon Blvd, 8" asphalt and stone		
18	450	SF	Pavement Demolition & Replacement Omni Blvd, 6" asphalt and stone		
19	340	SF	Pavement Demolition & Replacement Triton Court, 6" asphalt and stone		
20	540	SF	Pavement Demolition & Replacement Thimble Shoals Blvd, 6" asphalt and stone		
21	60	LF	Concrete Curb & Gutter Removal and Replacement		
22	1	LS	8" Pipe and Manhole Abandonment		
23	1	LS	Traffic Controls		
24	0.07	AC	Tree Clearing		
25	1	LS	Erosion and Sediment Control – Installation & Maintenance		
26	1,500	LF	Silt Fence (SF)		
27	6	EA	Street Storm Inlet Protection		
28	33	EA	Tree Protection		
29	1	LS	Mobilization/Demobilization		
30	43	LF	48" Manhole Coating System "Type B" Field Applied		
31	119	LF	60" Manhole Coating System "Type B" Field Applied		

Total Bid: _____

Bid Notes:

- 1) Refer to HRPDC Regional Construction Standards, Division 1, Section 109.1.1 "Incidental Items" for incidental work which may not be listed.
- 2) Contractor shall restore all pavement markings. This work is considered incidental.
- 3) Refer to the Hampton Roads Regional Construction Standards, Fourth Edition, as amended, dated October 2006 and Special Provisions Section in these specifications.
- 4) Manhole coating system shall be 80 mils Cor+Gard epoxy or approved equal. Product shall be applied by a manufacturer's certified applicator.

On acceptance of this proposal for said work, the undersigned does, or do hereby bind himself, or themselves, to enter into a written contract within ten (10) days of award, with the said Authority, and to perform said work for the consideration above named.

The bidder agrees to complete the entire work within **One Hundred Eighty (180) calendar days** from date of Notice to Proceed.

State Contractor Registration Number: _____

Business Name: _____

Address: _____
(Street; P.O. Box not acceptable)

(City, State and Zip Code)

By: _____ Date: _____

By: _____ Date: _____

ADDENDA
No.

ACKNOWLEDGED
Initial

IF CONTRACTOR DESIRES TO MAKE ANY ALTERNATIVE PROPOSAL ON DIFFERENT TYPE OF CONSTRUCTION THAN ONE CALLED FOR, IT SHALL BE ENCLOSED ON A SEPARATE SHEET.

CONTRACT
Canon Boulevard Sewer Trunk Line Improvements Project

Item #	Qty	Unit	Description	Unit Price	Total Price
1	310	LF	18" PVC Gravity Sewer Pipe 10-12' Depth, Installed Complete-in-Place		
2	426	LF	18" DIP Gravity Sewer Pipe 10-12' Depth, Installed Complete-in-Place		
3	299	LF	18" DIP Gravity Sewer Pipe 12-14' Depth, Installed Complete-in-Place		
4	375	LF	24" DIP Gravity Sewer Pipe, 12-14' Depth, Installed Complete-in-Place		
5	136	LF	16" DIP Gravity Sewer Pipe 14-16' Depth, Installed Complete-in-Place		
6	372	LF	16" DIP Gravity Sewer Pipe 12-14' Depth, Installed Complete-in-Place		
7	4	EA	48" Dia. Precast Concrete Manhole, 0-6' Deep, Installed Complete-in-Place		
8	19	VF	48" Dia. Precast Concrete Manhole, Additional Depth Over 6', Installed Complete-in-Place		
9	5	EA	60" Dia. Precast Concrete Manhole, 0-6' Deep, Installed Complete-in-Place		
10	4	EA	60" Dia. Precast Concrete Manhole, Straddle-type, 0-6' Deep, Installed Complete-in-Place		
11	65	VF	60" Dia. Precast Concrete Manhole, Additional Depth Over 6', Installed Complete-in-Place		
12	13	EA	Standard Manhole Frame and Cover, Installed Complete-in-Place		
13	1,800	CY	Select Material (CBR 20)		
14	4	EA	Connection to Existing Sanitary Sewer System		
15	1	LS	Dewatering		
16	1	LS	Fire Hydrant Relocation		
17	300	SF	Pavement Demolition & Replacement Canon Blvd, 8" asphalt and stone		
18	450	SF	Pavement Demolition & Replacement Omni Blvd, 6" asphalt and stone		
19	340	SF	Pavement Demolition & Replacement Triton Court, 6" asphalt and stone		
20	540	SF	Pavement Demolition & Replacement Thimble Shoals Blvd, 6" asphalt and stone		
21	60	LF	Concrete Curb & Gutter Removal and Replacement		
22	1	LS	8" Pipe and Manhole Abandonment		
23	1	LS	Traffic Controls		
24	0.07	AC	Tree Clearing		
25	1	LS	Erosion and Sediment Control – Installation & Maintenance		
26	1,500	LF	Silt Fence (SF)		
27	6	EA	Street Storm Inlet Protection		
28	33	EA	Tree Protection		
29	1	LS	Mobilization/Demobilization		
30	43	LF	48" Manhole Coating System "Type B" Field Application		
31	119	LF	60" Manhole Coating System "Type B" Field Application		

Total Bid: _____

Bid Notes:

- 1) Refer to HRPDC Regional Construction Standards, Division 1, Section 109.1.1 “Incidental Items” for incidental work which may not be listed.
- 2) Contractor shall restore all pavement markings. This work is considered incidental.
- 3) Refer to the Hampton Roads Regional Construction Standards, Fourth Edition, as amended, dated October 2006 and Special Provisions Section in these specifications.
- 4) Manhole coating system shall be 80 mils Cor+Gard epoxy or approved equal. Product shall be applied by a manufacturer’s certified applicator.

TECHNICAL SPECIFICATIONS

Modifications to Regional Construction Standards

Section	Title	Page	Subsection	Modification
Division 1		101-110		Division 1, Section 101 Thru 108 and Section 109.I.1.2 Thru Section 110 of the HRPDC Standards are deleted. The Department of Engineering Standard Specifications, Part One – General Requirements shall replace the deleted Division 1 of the HRPDC Standards. Division 1, Section I.1.1 “Incidental Items” is not deleted.
802	Sanitary Gravity Sewer Systems	802-3	II. Execution 2.2 Pipe Installation C. Pipe Laying	Add: “11. Pipe Connection A DFW/HPI non-shear coupling, Mission Flex Seal ARC Coupling, or approved equal shall be used between transitions of pipe materials and connections to existing pipe”.
802	Sanitary Gravity Sewer Systems	802-15	III. Measurement and Payment 3.2.A	Add: “3. Sanitary Main and Laterals All PVC pipe and fittings shall be ASTM 3034, SDR 26. Also included in unit price shall be allaying of dust during construction”.
802	Sanitary Gravity Sewer Systems	802-15	III. Measurement and Payment 3.2.A	Add: “4. Pipe bedding Construction shall use Type III pipe bedding stone for all sanitary gravity sewer pipe and sewer laterals. The price of bedding will be included with the unit price of pipe”.
802	Sanitary Gravity Sewer Systems	802-15	III. Measurement and Payment 3.2.C	Add: “3. Manholes The unit price shall also include ConShield additive to be used in the concrete mix as per the manufacturer’s recommendations on all concrete manhole sections and use of a geotextile fabric under the stone base”.
802	Sanitary Gravity Sewer Systems	802-15	III. Measurement and Payment 3.2.D	Remove this item
315	Asphalt Concrete Pavement – Non-Superpave	315-30	III. Measurement for Payment	Add: “3. Asphalt Concrete Asphalt concrete unit price shall include prime and/or tack coat”.
502	Concrete Items	502-6	III. Measurement for Payment 3.2.A	Add: “3. Combination Curb and Gutter Combination curb and gutter unit price shall include 6” aggregate base (Type 1, Size 21A)”.